Team 18

PURDUE POLYTECHNIC

Natco Transfer Line Restoration

<u>Purdue Students</u>: Sam Beaty , Sam Snyder , Alan Anderson, Daniel Gu, Mike La Bella, T revor Duncan, and Stone Campbell <u>Purdue Mentors / Customers</u>; Dave Merrick & David McMillan



Customer Background

The NATCO (National Automatic Tool Company) built large 'transfer line' automated manufacturing machinery. Many of the machines are still in operation today but the company has closed. This was a trade show demonstration unit that showed the functions of the system with automata movements. It is driven on the underside with a central power 'line shaft' very much like the factory lines of the generation before it.

Problem Statement / Scope of Work


The NATCO f actory transfer line model will have many different tasks to get the model restored and able to be displayed. In no order, the work includes cleaning the model, creating proper documentation of the model, creating displays, raising the model off the ground, making the model visually appealing, fixing the electronics, fixing the broken mechanical issues, creating a testing bench, and getting the model completely restored.

Requirements Matrix

Rest	DESIGN REQUIREMENTS	DESIGN TARGETS	VALIDATION	COMMENTS	
		Comments			
	Restoration of the model's electrical system to finational state.	Test the flore electrical sections of the model which are currently not in working condition.		Each circuit will need to be tested independently of each other and isolated from any other components that may be damaged.	
2	Incorporate push button start into model transfer line.	Install a posh button start. The push button start will trigger the model to move for a certain smorest of time.	mechanism and circuitry to prove	It will allow visitors and students to interact with the model without having to constantly run it. The model will run for no longer flam 60 meands when activated.	
з		The lights on the switchboard of the model do not correctly work and also difficult to find.	The lights will be acquired, built into the circuits, tested and connected through the push button	LEDs have the advantage of lasting for years without replacement. This adds to the longevity of the restoration.	
4	Replace the the model's secondary drive belt that transfers power from the motor to the front side drive shaft. Replace the belt that transfers the heads.	Install new secondary drive halt and courseyer belt that carries the bands from the end of the the model back to the begining. The belt will be replaced with rubber to mover reliability.	Will run the conveyor belt by running the electronics and mechanisms to make sure the belt does return the model engines	New subber helts will be much more relible than the orginal leather and reduce the maintence required on the model.	

Experimentation / Concepts Exploration





Final Design



<section-header>

Testing

Test	Req.	Test	Specifications &	Test	Test	Test	Test
ID	Matrix	Name	Test Method	Description	Stage	Requirement	Responsibility
1	1	Electrical Restoration	Functionality	The circuits will be tested independently to identify working and damaged components to repair to full functionality.	DV	No shorts, lights power up	Sam Beaty
2	2	Push Button Start	Activation	A push button will be tested to activate the model for one cycle.	DV	Model activates for one cycle	Sam Beaty
3	3	Underside Illumination	Illumination	LED lights will be tested to provide adequate lighting for the underside of the model.	PV	Entire underside of the model is adequately illuminated.	Sam Beaty
4	4	Informational Display	Readability	An informational display will be tested for grammar, readability, historical depth, and brevity.	DV	Display is easily readable with depth and brevity	Sam Beaty
5	5	Model Light Replacement	Activation	All lights on the model will be tested for activation	DV	All lights on the model power up when supplied voltage	Sam Beaty
6	6	Drive Belt Replacement	Functionality	The drive belt will be tested for durability and length to properly drive the model	DV	Model moves properly when the belt is moved	Alan Anderson
7	7	Panel Installation	Visibility	Side panels will be tested for low opaquness and visibility to the underside of the model	cv	Model underside is visible through side panels	Alan Anderson
8	8	Stand Installation	Height and Visibility	Stand will be installed to elevate the model and provide improved visibility to model underside	cv	Model is elevated 12-18 inches and is more observable	Alan Anderson
9	9	Station Reconnection	Functionality	Each mechanical station will be tested when the motor activates, seeing if they move smoothly during the transfer line run time.	PV	The stations are able to move fluidly with no issues	Sam Snyder